



RIDGE CAP. HOOK ON Z CLOSURE BOTH SIDES

Z CLOSURE. BED ON CONT. CUT TO FIT BETWEEN PANEL RIBS. BED ON CONT. BUTYL TAPE SEALANT. FASTEN THROUGH TO SHEATHING W/ FOUR (4) #12 WOOD SCREWS PER PANEL. SEAL ALL HORIZ. & VERT. MATING SURFACES W/ APPROVED ROOFING SEALANT

PAC-150 ROOF PANEL

PAC-150 ROOF PANEL CLIP (FIXED OR EXPANSION PER PROJECT REQUIREMENTS) ON BEARING PLATES IF OVER RIGID INSULATION. FASTEN THROUGH TO STEEL DECK W/ TWO (2) #14 SCREWS PER CLIP

SUB-RIDGE PLATE

UNDERLAYMENT

RIGID INSULATION

STEEL DECKING

ROOFING SHOP  
DRAWINGS BY



PAC CLAD  
PETERSEN ALUMINUM CORPORATION

102 NORTHPOINT PARKWAY, BLDG 102  
ACWORTH, GA 30102  
PH: 77-0427-6378 FAX: 770-420-2533

JOB

DETAIL

PAC-150 RIDGE ASSEMBLY 2

SCALE  
N.T.S.

ARCH REFERENCE  
N/A

FILE #  
DLT

DATE  
29 MAR 2015

SHEET